

Stabilizing Slides in Pennington Formation with Drilled Ground Anchors

Site

Slope Stabilization @ I-40 WB MM 342, Roane Co.

Geotechnical Engineer: WSP\Golder

Contractor: Goettle

Contract: CNU 224

Presenter: Robert Jowers, PE



Photo Source: TDOT






Photo Source: George Hornal\TDOT

Presentation Agenda

- ❖ **TDOT geohazard**
 - **Pennington Formation colluvium**
- ❖ **Extensive site characterization and plans development effort**
- ❖ **System components used and schedule of progress**
- ❖ **Ground anchors could be a new slope stabilization tool at TDOT**

Background



Source: Moore, H., "A Geologic Trip Across Tennessee Interstate 40", University of Tennessee Press, 1994

- ❖ **Geology \ Geography Creates Divisions**
- ❖ **TN contains nine physiographic regions**


Geology

- ❖ Pennington Shale Formation Test Boring (1/3
- ❖ Notice the color on the drill matching the test boring samples



Source: TDOT

Geology




Source: David Grooms\David Royster\TDOT

- ❖ **Contains predominate shales that tend to weather differentially with overlying Gizzard Group Sandstone**
- ❖ **Creates unconsolidated colluvium, containing sandstone cobbles to boulders**
- ❖ **Through mapping, Golder identified an upper sandstone member, and a lower shale member**
- ❖ **The subject colluvium is more pervious than underlying strata – so trapped water pressures are created**

Source: Golder \ TDOT

Geology

If there is a practical colluvium depth, the landslide can be stabilized practically.



Source: TDOT



Source: George Horna\TDOT

I-40 Construction in 1968

- ❖ South of Walden Ridge, near the city of Rockwood
- ❖ Fill Slide proposed near MM 341.5-342
- ❖ Halted Construction



Source: George Hornal \ TDOT

I-40 Construction in 1968

- ❖ **Entire corridor is built on unstable colluvial material**
- ❖ **Must contend with the Pennington Shale colluvium**



Source: George Horal \ TDOT

I-40 Rockwood Corridor Maintenance Time Line

- ❖ **Slope movement continues**
- ❖ **1970's TDOT later installed drilled horizontal drains**
- ❖ **2012 Deep wells were installed**
- ❖ **2017 Replaced pinched off inclinometers**
- ❖ **2018 Future plan of action could be drastic \ significant - drilled ground anchors**

Landslides Triggered Feb. 22, 2019

Historic Flooding Across The Tennessee Valley

February 22-23, 2019

Radar loop of composite reflectivity


from early morning through mid afternoon (click to enlarge)



Landslides Triggered

- ❖ **Feb. 22, 2019 Rain Began**
- ❖ **Over 100 Landslides Occurred because of flooding**
- ❖ **Two Sites along EB and WB were identified that required immediate stabilization repair – Project Site**

Landslides Triggered



❖ **I-40, Roane Co. Project Site shown in red circle**

National Weather Service (2019). *February 2019 Rainfall Compared to December 1926 Rainfall*. Retrieved from <https://www.weather.gov/ohx/February2019vsDecember1926>

Practical Landslide Stabilization

RESTRAINT

Practical Landslide Stabilization

Restraint

- Stone Buttress
- Soldier pile lagging retaining walls (often w\ drilled anchors)
- Reticulated micropiles (used to bridge terrain in Foothills Pkwy)

Royster, D. L. (1978). Landslide Remedial Measures. *Prepared for Presentation at the 37th Annual SASHTO Convention, October, 1978, Nashville, Tennessee*



Restraint – Stone Buttnress

- ❖ **Earthwork Volume excessive**
- ❖ **Practical if colluvium shallow**
- ❖ **Typically requires road closure**
- ❖ **Impractical in urban \ high ADT**

Source: Barry McClendon, TDOT R2 Survey Office, August 6, 2019




Restraint – Stone Buttress

❖ SR-85, Fentress Co.

Source: Barry McClendon, TDOT R2 Survey Office, August 6, 2019


Restraint – Drilled Anchors



Source: FHWA, GEC Circular No. 4, Ground Anchors and Anchored Systems, 1999

- ❖ **Practical – But major investment**
- ❖ **Costs and benefits warrants investment on interstate slopes**

Project Vicinity



Source: Golder \ TDOT

Project Vicinity

- ❖ Slope movement occurs
- ❖ Further downhill 1.25 mi. – eastward
- ❖ Two separate slides
- ❖ KS Ware retained to develop plans I-40 EB MM 343 (+\ -)
- ❖ Golder retained to develop plans I-40 WB MM 342 (+\ -)

EB Project Design

- ❖ KS Ware's EB MM 343 site utilized ground anchors supporting a soldier pile \ lagging wall
- ❖ Bid just under \$3.5
- ❖ Good administration
- ❖ Straight forward, single anchor row




Source: TDOT



Source: TDOT

EB Project Construction Phase Retaining Wall Complete

November 2021



Source: Golder \ TDOT

WB Site Characterization

Much Larger Area

❖ Extensive Site Characterization Required

❖ Thirty-five test borings


❖ Developed six slope inclinometers



Source: Golder \ TDOT

WB Site Characterization


- ❖ Extensive Site Characterization Required
- ❖ Thirty-five test borings
- ❖ Developed six slope inclinometers
- ❖ Twenty-two vibrating wire piezometers



Source: Golder \ TDOT

WB Site Characterization

- ❖ Extensive Site Characterization Required
- ❖ Thirty-five test borings
- ❖ Developed six slope inclinometers
- ❖ Twenty-two vibrating wire piezometers
- ❖ Three electrical resistivity lines



Source: Golder \ TDOT


WB Site Characterization

- ❖ Extensive Site Characterization Required
- ❖ Thirty-five test borings
- ❖ Developed six slope inclinometers
- ❖ Twenty-two vibrating wire piezometers
- ❖ Three electrical resistivity lines
- ❖ Detailed geological mapping


WB Site Characterization

- ❖ Extensive Site Characterization Required
- ❖ Thirty-five test borings
- ❖ Developed six slope inclinometers
- ❖ Twenty-two vibrating wire piezometers
- ❖ Three electrical resistivity lines
- ❖ Detailed geological mapping
- ❖ Using sophisticated geologic modeling software - LeapFrog
- ❖ Identified Four significant slides

Source: Golder \ TDOT




WB Design Analyses



Source: Golder \ TDOT

- ❖ Deep Colluvium – Significant
- ❖ Fifty-feet grid



Source: Golder \ TDOT



STA: 26+57.6 @ I-40 WB
SECTION J - J'

Contract Plans Design

❖ Acceptable Type of Earth Retention:


Ground Anchors with
Concrete Bearing Blocks

❖ Full Anchor Schedule Design – @ 1700!

❖ Drill depths between approx. 150 ft. and 250ft.

WB Plans Design - Anchors

- ❖ Bid plans required 3, 7, and 9 Strand cable
- ❖ Design loads of 80 kip, 246 kip and 317 kip
- ❖ Drill depths between approx. 150 ft. and 250 ft.



Source: Golder \ TDOT



Source: TDOT

WB Plans Design – Concrete Blocks

- ❖ 1,700 Concrete Blocks
- ❖ Designed by Contractor using design guidance in plans
- ❖ Contractor to submit shop drawing design for approval to Engineer
- ❖ Foundation improvement specified incidental to cost of block item

Project Bid

- ❖ Two Sites combined & Bid
- ❖ Design-Bid-Build contract
- ❖ Bids Opened May 15th, 2020
- ❖ Apparent Low Bid of \$33 M
- ❖ Awarded to Goettle, Inc.

Index Of Sheets
SEE SHEET NO. 1A

THIS PROJECT TO BE BRACKETED WITH:
ROANE COUNTY I-40 (EB)
PIN: 128668.00
ER-NH-I-40-6(172); 73100-4131-04

STATE OF TENNESSEE DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING

ROANE COUNTY

I-40 WESTBOUND: NEAR MM 342 TO NEAR MM 344
(SLOPE STABILIZATION) (FEBRUARY 2019 FLOOD)


CONSTRUCTION
REPAIR SLOPE FAILURE, GRADE, DRAIN, AND RESURFACE
STATE HIGHWAY NO. N/A U.S. ROUTE NO. N/A

DOES THIS PROJECT QUALIFY FOR UTILITY CHAPTER 86	YES	NO X
WORK ZONE SIGNIFICANCE DETERMINATION	YES	NO X
SIGNIFICANT	YES	NO X

TENN.

FED. AID PROJ. NO.

STATE PROJ. NO.



NO EXCLUS




73100-4130-04
ND PROJECT NO. ER-NH-I-40-6(173) CONSTRUCTION
TA. 45+05.00 MILE MARKER: 342.6
572126.3714 E 2366854.2597

PROJECT OF LIMITED SCOPE

73100-4130-04
EGIN PROJECT NO. ER-NH-I-40-6(173) CONSTRUCTION
TA. 8+20.00 MILE MARKER: 343.3
571133.8960 E 2363361.4487

SPECIAL NOTES

ALLS MAY BE REJECTED BY THE COMMISSIONER IF ANY OF THE UNIT PRICES
IED THEREIN ARE OBVIOUSLY UNBALANCED, EITHER EXCESSIVE OR BELOW
SONABLE COST ANALYSIS VALUE.



I-40 WB

SURVEY 04-14-19	TRAFFIC DATA
ADDITIONAL 07-25-19	AOT (2019) 17,020



APPROVED: *Paul D. I*

PAUL D. I

DATE:



APPROVED: *Ch*

CLA

U.S. DEPARTMENT
FEDERAL HIGHW.

Project Const. Admin. - VECP

- ❖ Contractor presented Value Engineering Change Proposal
- ❖ Construction companies have different equipment available
- ❖ Different work schedules



Project Const. Admin.-VECP

- ❖ **Decrease number of concrete blocks to about 600**
- ❖ **Increase the tension load significantly**
- ❖ **Pennington Shale's ability to meet stress transfer**
- ❖ **No test load data**
- ❖ **Known knowns: Inaccessible and Tough Drilling**

Source: Shop Drawings Value Engineering Anchor Stabilization System, I-40 (WB) Near 342, June 17, 2022, Goettle \ Burns Cooley Dennis, Inc. \ TDOT

TA1 TEST SETUP




Project Const. Admin - VECP

- ❖ Prior to consideration, TDOT required load tested anchors
- ❖ Design loads of 500 k were applied
- ❖ 12 strand anchors
- ❖ 8 in. diameter
- ❖ *VECP approved*

Source: Shop Drawings Value Engineering Anchor Stabilization System, I-40 (WB) Near 342, June 17, 2022, Geottle \ Burns Cooley Dennis, Inc. \ TDOT

Project Const. Admin - VECP




❖ Initial design based on quality site characterization

❖ Added value to the project - solid

❖ The slip surface \ minimum anchor free length evaluated

❖ Strategic bearing strata location was evaluated

Anchor Drilling



Anchor Drilling

TYPICAL SECTION



Anchor Drilling




Anchor Drilling

October 2021




Anchor Drilling – Measuring Inclination

OCTOBER 2021



Anchor Drilling - Concept

TYPICAL DETAIL SECTION



NOTES

1. TO BE READ IN CONJUNCTION WITH THE NOTES SHEETS AND CONTRACT DOCUMENTS.
2. AT THE START OF CONSTRUCTION, AT LEAST ONE PERFORMANCE TEST AND EXTENDED CREEP TEST SHALL BE PERFORMED ON EACH TYPE OF ANCHOR DESIGN AND ANCHOR MATERIAL. IF DESIGN CHANGES ARE NEEDED AS INDICATED BY THE PERFORMANCE TEST RESULTS, THE SAME TESTS SHALL BE PERFORMED ON ANCHORS WITH REVISED DESIGN. PERFORMANCE TESTING SHALL BE PERFORMED ON 5% OF REMAINING ANCHORS.

Anchor Drilling - Strand Placement

TYPICAL DETAIL SECTION



Anchor Drilling - Strand Insertion

August 2021

Concrete Blocks



Concrete Blocks – Pre-Cast Site

December 2021



Concrete Blocks – Set In Place using Crane

October 2021



Concrete Block - Final Position

December 2021

Concrete Blocks – Next Bench Excavation

MAY 2022





Anchor Stressing & Load Testing



Anchor Stressing & Load Testing

December 2021

Source: TDOT



Anchor Stressing & Load Testing

December 2021

Source: TDOT

Anchor Stressing & Load Testing



Anchor Stressing & Load Testing

Anchor Proof Test

Stranded Anchors

Anchor Drill Date: 8-Oct-21

Jack Capacity, tons: 600

Job No. 20001

Test Date: 6-Nov-21

Jack calibration date: 22-Jul-21

Job Name: CNU224

Anchor No.: 3B30

pump used: HP= 88

Location: Hamman, TN

Anchor Zone: 3

ram used: HR= 66

General Contractor: Richard Goettle, Inc.

Location: WB SLOPE

Jack-ram set-up #: 1

Anchor Contractor: Richard Goettle, Inc.

Anchor Block Lot #: 5

max elongation, in: 9.257

Anchor Block Size: 10' x 8'

TENDON DATA			%DL	AL	25	50	75	100	120	133
ANCHOR DESIGN LOAD 421.8 Kips			LOAD	63.3	105.5	211.0	316.4	421.9	506.3	561.1
BOND LENGTH 30 ft			ELONG'N	-	0.820	2.210	3.736	6.272	8.982	7.886
FREE LENGTH + JACK SETUP (6 FT) 100.0 ft			d MIN (in)	0.000	0.546	1.910	3.275	4.639	5.730	6.440
TAIL LENGTH 10.0 ft			d MAX (in)	0.000	0.785	2.746	4.707	6.668	8.237	9.257
ANCHOR STRAND QUANTITY 12			gauge, psi	880	1,100	2,130	3,180	4,180	6,010	6,640
TOTAL STRAND AREA 2.80 in ²										
MODULUS OF ELASTICITY 28,600 ksi										
CREEP TIME:			1	2	3	4	5	6	10	15
TEST	READING:	7.886	7.888	7.871	7.872	7.873	7.874	7.876	-	-
INFO	CREEP:	-	0.004	0.006	0.007	0.008	0.009	0.010	-	-

CREEP READINGS


1 to 10	0.010	OK
6 to 60	-	-

LOCK-OFF (100 % D.L.)

target	actual	
421.8	423	kips
4,190	4,200	psi

ELASTIC ELONGATION (in)


Total Elongation	7.665
AL After Backing Off MTL	0.469
Elastic Movement @ MTL	7.196



STRANDS

Unit Strand Area: 0.217 in²

E= 28,600



COMMENTS:

Test Tech: Cody Schappacher

Anchor Stressing & Load Testing



CNU224 - I40 Slope Stabilization

ZONE 2

ZONE 3

ZONE 4

Instances	% of Total
260	42.98%
38	6.28%
0	0.00%
0	0.00%
303	50.08%
4	0.66%
605	100.00%

1st Day Drilling	8/5/2021
Days Elapsed Since	312
Avg. Anchors Approved Per Calendar Day	0.97
Projected Anchor Completion By Straight Line Interpolation	4/19/2023

Anchor Stressing & Load Testing

Tracking Progress using Excel

19	1-A18	4	TDOT Acceptance	PAID	20	4/20/2022
20	1-A19	4	TDOT Acceptance	PAID	20	4/20/2022
21	1-A20	4	TDOT Acceptance	PAID	20	4/20/2022
22	1-A21	4	TDOT Acceptance	PAID	20	4/20/2022
23	1-A22	4	TDOT Acceptance	PAID	20	4/20/2022
24	1-A23	4	TDOT Acceptance	PAID	20	4/21/2022
25	1-A24	4	TDOT Acceptance	PAID	20	4/21/2022
26	1-A25	4	TDOT Acceptance	PAID	20	4/21/2022
27	1-A26	4	TDOT Acceptance	PAID	20	4/21/2022
28	1-A27	4	TDOT Acceptance	PAID	20	4/21/2022
29	1-A28	4	TDOT Acceptance	RRENT ESTIMA	21	5/19/2022
30	1-A29	4	TDOT Acceptance	RRENT ESTIMA	21	5/19/2022
31	1-A30	4	TDOT Acceptance	RRENT ESTIMA	21	5/19/2022
32	1-A31	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
33	1-A32	0	Not Installed	NOT PAID	NOT YET PAID	
34	1-A33	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
35	1-A34	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
36	1-A35	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
37	1-A36	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
38	1-A37	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
39	1-A38	1	Installed, Not Tested	NOT PAID	NOT YET PAID	
40	1-A39	0	Not Installed	NOT PAID	NOT YET PAID	
41	1-A40	0	Not Installed	NOT PAID	NOT YET PAID	
42	1-A41	0	Not Installed	NOT PAID	NOT YET PAID	
43	1-A42	0	Not Installed	NOT PAID	NOT YET PAID	
44	1-A43	0	Not Installed	NOT PAID	NOT YET PAID	
45	1-A44	0	Not Installed	NOT PAID	NOT YET PAID	
46	1-B1	4	TDOT Acceptance	RRENT ESTIMA	21	5/18/2022
47	1-B2	4	TDOT Acceptance	RRENT ESTIMA	21	5/18/2022
48	1-B3	4	TDOT Acceptance	RRENT ESTIMA	21	5/18/2022

Anchor Stressing & Load Testing

Tracking Progress using Excel


Progress Time Line



Progress Time Line

APRIL 2021

Source: TDOT



Progress Time Line

OCTOBER 2021

Source: TDOT



Source: TDOT

Progress Time Line

NOVEMBER 2021



Source: TDOT

Progress Time Line

JANUARY 25, 2022



Source: TDOT

Progress Time Line

MARCH 16, 2022



Progress Time Line

APRIL 19, 2022



Looking West at Zone 3

MAY 2022



Looking East at Zone 3

MAY 2022



Progress Time Line

JUNE 14, 2022



Progress Time Line

AUGUST 16, 2022

Status Key	Status Number	Indication	Instances	% of Total
	0	Not Installed	57	9.42%
	1	Installed, Not Tested	37	6.12%
	2	Installed, Tested, Pending Test Submission	0	0.00%
	3	Pending TDOT Acceptance	0	0.00%
	4	TDOT Acceptance	511	84.46%
			605	100.00%
Status Date		9/6/2022		

1st Day Drilling	8/5/2021
Days Elapsed Since	397
Avg. Anchors Approved Per Calendar Day	1.29
Projected Anchor Completion By Straight Line Interpolation	11/18/2022



End of Presentation – Time for Questions?