Louisiana DOTD Geotechnical Database Efforts

Gavin P. Gautreau, P.E.

Sr. Geotechnical Research Manager


Louisiana Transportation Research Center (LTRC)





LTRC Introduction

- LTRC was created by Louisiana Legislature in 1986.
- Sponsored Jointly by the Louisiana Department of Transportation and Development (DOTD) and Louisiana State University (LSU)
 - Conduct short- and long-term research
 - Provide technical assistance, training, continuing education, technology transfer to DOTD and the transportation community.
- Research Problem Identification Committees (RPIC)
 - Problem Solicitation (every 2 years)
 - Committee Review & Rating → Work Program
 - Importance & Implementation Potential
- Project Review Committee (PRC)
 - Industry, Academia, and Government



Data Management

... Data is an Asset!



1986 gINT (The Geotechnical Integrator) Founded

19XX DOTD Begins Using gINT



~1998 DOTD Starts saving .pdf copies of boring logs



2003 - Phase I LTRC In-House Research

PDFs (information) to ArcMAP

- Non-GIS website with searchable fields.
 - Links to documents (DOTD Content Manager)
- GIS based website
 - Links to documents (DOTD Content Manager)
- Custom Code and ArcGIS versions

www.LTRC.LSU.EDU
LTRC Project # / Re port #





2007 STGEC – Bowling Green, Kentucky ...KYTC work 2009 Bentley acquires gINT



Louisiana Digital Data

2010 - Phase II Dataforensics

- gINT software customization
- Better / Digital logs
- Standardized data
- gINT Template shared with labs for uniformity
- pLOG & Rapid CPT







LTRC Project # / Report #

www.LTRC.LSU.EDU



2015 - Phase III Dataforensics

www.LTRC.LSU.EDU LTRC Project # / Report #

- Pile Load Test Database Organization
- DOTD District Shallow Soil Borings
 - Standardization of data and reports
 - HoleBASE, Keynetix
 - KeyLAB, Keynetix



- DOTD Districts are independent
- Geotechnical Design saw potential in HoleBASE for Deep Borings










2020



2020 Bentley Releases Open Ground Cloud

2021 – Phase IV LTRC In-House

DOTD Deep Borings Implementation to HoleBASE

- LTRC Data Upload/Conversion
- KeyLAB, (internal drill crew)
- HoleBASE to OpenGround Migration
- Dataforensic (Bentley Rep)



Capsule



Dataforensics



Data Strategy "Road Map"

Data Baskets

- .pdfs DOTD Geotech Files
- .pdfs DOTD Content Manager
- gINT files Materials Lab
- gINT files Section 67
- gINT files Consultants
- Pile Load Test Data
- Others

Excel Spread Sheets

- Monitor Progress (Uploads/Conversions to OpenGround)
- Address Problems (Identify, Categorize, Resolve)

Communications


- Meetings with LTRC & DOTD Geotech (every other week)
- Meetings with Dataforensics, Bentley Rep (Monthly)
- LTRC Guidance Documents How to Convert / Upload







PDFs (Information)

- Information still has value
- Uploads to OpenGround
 - Technician Effort (Chris Mertz, LTRC)
 - Checked uploads for Accuracy
 - Project Information
 - Design #, Construction #, H.000000#
 - Location:
 - GPS Centroids
 - Pre GPS (used Structure # and Road Control Section)
 - Some were culverts, not bridges
 - Splitting Borings (Triple Panel Log) into distinct projects
- Future Effort: Use Artificial Intelligence (AI) and Optical Character Recognition (OCR) to convert *.pdf borings into <u>Digital</u> data.



Geotechnical Database - Phase IV (21-2GT)







Project No.: Project Name: Project Location: Structure/Recall:

61242570101101

H.009484 Parish: IBERVILLE
LA 75: BAYOU BREAUX BRIDGE

Route: LA 75 Martin Luther King Jr Pkwy

Boring: B-0
Latitude: 30.22
Longitude: -91.10
Elevation: 17.81

B-01 1/3 30.228860 -91.101870 17.8 ft

	_				_	ı	-			ı
Depth [ft]	Bevation [ft]	Graphic	Material Description & (USCS)	Sample ID	Pocket Pen/ Torvane [tsf]	Comp. Str. [tsf] @ o² [psi] / SPT [bl/ft]	Failure Mode / SPT Termination	Fines Content [%]	ywet [pcf]	Moisture Content & Atterberg Limits
٥	B	_		, v	8 Þ	S @ 52	Failt	Ē	3	● MC [%] —— PL & LL [%] 20 40 60 80
		////	Stiff, gray, LEAN CLAY (CL)	C23		1.43	M.S.	89	120	
E	4			(23		@3	M.S.	89	120	
Ŀ	-									
ŀ.										<u></u>
-5	13		Medium stiff, gray, FAT CLAY (CH)	504	1	0.91				
E				C24		@7	s/s	97	114	
Ŀ	-									
Ė	-									
10	8		Gray, SILT (ML), Org = 5%		1	1.05				
Ė]		, (,	C25		@11	M.S.	97	125	
Ŀ	4			Γ						
Ŀ	-									
-15	3		Gray, SANDY SILT (ML)		-	0.46				
F]		Gray, Grand Folker (Inter)	C26		@15	M.S.	62	123	
Ē				Γ						
Ŀ	-									
-20	2		Gray, SILT WITH SAND (ML)		-	1.21				
ļ-]		Gray, Sier Williams (Me)	C27		@19	M.S.	75	121	
Ē]			Γ						
Ŀ	4									
-25	7		Loose to medium dense, gray,			1-3-4				
į.	7		SANDY SILT (ML)	D28		(7)		65		
F]									
E										
-30	-12					2-5-5				
-				D29		(10)		57		
F]									
E										
-35	17		Company Company							
-	-		Gray, SILT WITH SAND (ML)	C30		0.23 @32	M.S.	76	126	
F]			F		2002				
E]									
<u> </u>										

Drilling Contractor: LADOTD statewide drill crew (Under Section 67) Start / Complete: 11/14/2017 / 11/14/2017 Driller/Logger: Mike Anderson Groundwater Levels: LADOTD Simco 2800 Equipment: Automatic Hammer ☑At time of drilling - No Water Level Taken Hammer Type: Efficiency: Drilling Method: Wet-Rotary Backfilled with cement bentonite grout. Backfill Method: Remarks: Original survey in boring log is incorrect. Updated survey from Google Map based on borehole grouted location.




Cone Reference:

Backfill Method:

Project No.: Project Name: Project Location: Structure/Recall: H.009484 Parish: |BERVILLE Boring:
LA 75: BAYOU BREAUX BRIDGE Latitude:
Longitude:
Route: |LA 75 Martin Luther King ir Plwy
Elevation:

CPT-01 _{1/} 30.228861 -91.101839 17.24 ft




Cone Area Ratio: 0.80

Backfilled with cement bentonite grout.


Remarks: CPT pushed to investigate presence of pile driving

obstruction at an adjacent bent location 20' away.


OpenGround Cloud (OGC) Excel Extension




Geotechnical Data Plots – OGC Excel Extension



Geotechnical Data Plots – OGC Excel Extension



KeyLAB



DOTD is implementing KeyLAB internally.

- Laboratory Information Management System (LIMS)
 Pending ~ Several Years Away **OpenLAB**?
- KeyLAB transition to future "OpenLAB"
 - Migration should be easy...excel based...Bentley starting point.
- OpenGround Portal Data Entry is expanding



Geotechnical Work Flow - QA/QC & Reporting

DOTD Materials Lab (Drill Crew & Lab)

- Dataforensics:
 - "Road Map" Guidance on Big-Picture
 - KeyLAB custom templates (DOTD format, ASTM)
 - KeyLAB Training (Lab and Engineers)

Geotechnical Data Report (GDR)

- Logs (CPT, Boring)
- Other tests, etc.
- Supporting Data
- DOTD Lab and Consultants will be required to digitally submit Geotechnical Data Reports (GDRs).

Section 22 Materials Laboratory - Data Review

- * Login to OGC and select project
- * Verify CPT data import by Section 67
- * Review and update "Location Details" table
- * Review and complete "Field Geological Descriptions Soil" table
- * Export necessary charts, boring logs, and site plans from OGC.
- "Log Report" button w/ "Geotechnical Data Report"
- * Plot soil borings logs
- Use "DOTD Soil Boring Log (8.5 x 11)" template
- * Plot CPT sounding logs
- Use "DOTD CPT Log (8.5 x 11)" template

Section 22 Materials Laboratory - Data Report

- * Prepare the Geotechnical Data Report (GDR) in accordance with Chapter 15 of the Geotechnical Design Manual (GDM).
- * Submit Draft GDR to Section 67 for review and acceptance via e-mail.

Section 22 Materials Laboratory - Data Report

* Update the GDR- to address any outstanding comments

LTRC

Section 22 Materials Laboratory - Data Report

* Submits a signed and sealed GDR to Section 67 via email

Geotechnical Engineer - Data Review

via email to Section 22.


* Review the report, logs, and OGC data

* Provides either comments or acceptance

Geotechnical Engineer

* Uploads the GDR into FileNET and FALCON.

Other visualizations and analyses




OpenGround to OpenRoads

from Bentley Civil User Conference 2024



OpenRoads Geotechnical Extension

OpenRoads Geotechnical Extension: For a tight integration between OpenGround Subsurface data and Bentley Civil Design Products.





Data Interchange for Geotechnical and Geoenvironmental Specialists (DIGGS)



The DIGGS project involves development of a GML (XML-based) geospatial standard schema for the transfer of geotechnical and geoenvironmental data within an organization or between multiple organizations.

DIGGS can work with existing software, hardware, databases and data storage facilities to easily transfer and share your data.



Consultants/DOTs

GIS

- **DOTD Sections**
- **Plans**
- **Public**
- **BIM** Digital Twins

LTRC Project: 24-2GT

"GEC-5"

WEB-based tool to Advance Geotechnical Data Interchange and Reliability-Based Site Characterization

LTRC: DOTD, Gavin Gautreau, Nick Ferguson, Technicians

LSU, Murad Abu-Farsakh, Research Associates, etc.

GeoSyntec: Xin Peng

Project Review Committee insight

DOTD: Section 67, Geotechnical & Section 22, Materials Laboratory **Dataforensics**, Scott Deaton (Bentley-OGC Representative)



Web-Based Visualizations



 Data Management & DIGGS Data Interchange for Geotechnical and Geoenvironmental Specialists

GEC-5 Geotechnical Engineering Circular (GEC)
 No. 5 (AASHTO Updates)



LTRC Project: 24-2GT

Objectives

Web-Based Visualization

Finalize/formalize a web-based platform used by DOTD for several large projects...to standardize this visualization process for all projects.

- Interactively visualize and interpret data from soil borings, CPTs, geophysical/conventional data.
- Create composite soil stratigraphy
- Plot soil properties and derived parameters vs. elevation
- Develop design profiles.



LTRC Project: 24-2GT

Objectives


Data Management & DIGGS Data Interchange for Geotechnical and Geoenvironmental Specialists (DIGGS) - Implementation

- DOTD → OpenGround & KeyLAB (Phase IV)
- DOTD Contract Consultants → ...maybe OpenGround? (other solutions)
 - gINT Sun-setting
 - Data transfer & exchange (new and historical data)
 - Proactive solution for DOTD and its consultants
- Implement a web-based platform with visualizations for standardized exchange to efficiently increase the quality of geotechnical data deliverables as a digital asset.




AASHTO LRFD Bridge Design Specifications

- Section 10 Rewrite
 - 2023 STGEC Scott Hidden, NCDOT
 - 2024 SWGEC- Jesse Rauser, LADOTD



values with COV_{Model}≤0.3 reliability that practically design according to the AASHTO LRFD Bridge Design Specifications."



Conclusions

- Advancing DOTD Geotechnical Data Management
 - Accessing data easily via OpenGround GIS Interface
 - Improving current, functional Effectiveness & Efficiencies
 - Building Long-Term Database Reference & Correlations
 - Planning Succession, Knowledge Transfer & Retention
 - Connecting Data Sources (Scour, Pile Load Tests, LiDAR, Materials, etc.)
- Leadership & Vision: Jesse Rauser, DOTD Geotechnical
 - LTRC facilitation (20+ years) to advance DOTD Geotechnical Data Management

Thank you!

Questions?

Part Two Xin Peng

