

US 76/SR 2 (Lookout Mountain Scenic Highway) Landslide Repair in Rabun County, GA

Eugene Utsalo, P.E.


Geotechnical Branch Chief
Office of Materials & Testing

Outline

- Construction Problem
 - Project background
 - What happened
 - Challenges
- Design Solution
 - Tie-back wall
 - Geotechnical exploration
 - Stability analysis
- Lessons Learned
 - Takeaways
 - Cost

Project Location

- From the TN line (Ridges & Valley) through the Chattahoochee-Oconee National Forest to the SC line (Blue Ridge)
- High priority with low to medium AADT - 1,730/16 (2021), 2,750/14 (2022) & 2,810/14 (2023)



Project Background


- Roadway within project limits had a history of pavement distress repairs
- Significant pavement cracks, bulges & localized failures observed in May of 2019
- Landslide observed during field investigations
- Emergency project



Aerial View of Landslides



North Slide




South Slide



Landslide Cause

Caused by groundwater seepage



Initial Challenges


1. Coordination with US Forest Service
 - Chattahoochee-Oconee National Forest

2. Cold water trout streams down existing slope
 - Disturbance of approximately 2.18 acres

3. COVID-19
 - Social distancing and precautions

Design Solution


Tie-Back Wall



Geotechnical Exploration


Subsurface & Wall Foundation Investigations

- SPT Borings
- CPT Borings
- Slope Inclinometers
- Piezometers



Subsurface Features

- Topsoil
- Fill soils, colluvial and residual soils
- Partially Weathered Rock (PWR)
- Bedrock



Tie-Back Wall Design

Excavation for wall installation

Soldier piles (14x89) - spaced 7 feet
& embedded 3 to 16 feet into mostly
PWR

Tie-back anchors embedded 10 to 12
feet into PWR & rock; bonded length
→ 40 to 90 feet

Horizontal drains - lower water table &
porewater pressures





Tie-Back Wall Design Advantages

- Increased structural capacity
- Long-term durability
- Non-complex installation process
- Cost-effective

Tie-Back Wall Global Stability

- Global Stability Analysis showed Tie-Back Wall with anchors embedded in PWR/rock exceeded the desired Factor of Safety



Construction

- Roughly 2.5 years
 - Start - October of 2021
 - End - April 2024
- COST
 - Preliminary Engineering - \$250,000 (~\$325,000)
 - Construction - \$10.6M (~\$10.5M)
 - Total - \$10.85M (~\$10.84M)

Final Wall Section



Lessons Learned

1. More communication between maintenance and design
2. Importance of an Asset Management Program



Thank You