



The Project – Quick Facts

Existing bridge:

- Built in 1930, out of service since 2008 due to age and structural deficiency.
- 960 feet long w/ 15 conventional concrete beam spans over land and 4 steel truss spans over the river.
- All foundations are spread footings on IGM/Rock

New bridge:

- 975 feet long w/ 8 spans
- Piers are column extensions of drilled shafts
- 2 drilled shafts per pier, 5 drilled shafts per abutment
- Schedule NTP Sept 2024, est complete Aug 2027
- Cost \$22 million
- Designed by Lynchburg District S&B/CO S&B Geotech




Project Location






Project Location





Existing Bridge Plans



Note: all foundations are spread footings



Existing Bridge Photos













Existing Bridge Demolition







So how, there is no audio when I emailed it to myself. I think it is ok without audio. Vester, Robert (VDOT), 2025-09-05T15:09:54.931 VR0

New Bridge Plans











Geology

- Carolina Slate Belt (Piedmont Physiographic Province)
- Site underlain primarily by the Aaron Formation and the Hyco Formation on Halifax County (north) side.
 - Upper Aaron: phyllite & slate
 - Lower Aaron: primarily metaconglomerate & metasandstone.
 - Hyco: primarily schist, metatuff and greenstone.



Slide 10

VRO This statement is confusing. Are we trying to say the Aaron formation is on the Charlotte County side (south side)?

Vester, Robert (VDOT), 2025-09-05T14:43:04.723

VR1 Metastuff?

Vester, Robert (VDOT), 2025-09-05T14:43:15.645

Geology





Subsurface Exploration

- 2 to 4 borings per substructure unit
 - Abutments: Depths 73 ft to 103 ft (avg 87 ft)
 - Piers: Depths 35 ft to 95 ft (avg 56 ft).
 - Rock coring length of 15 to 50 ft (avg 35 ft).
- Some discrepancies with differentiation of IGM and highly fractured rock were observed.
- Several supplemental borings were conducted to clarify this discrepancy.



VR0

As an aside during the presentation, may want to further discuss how drilling technique is important in exploration of this type of rock. Fast drilling with large crowd can break down the material into an IGM. Slower, less crowd tends to produce more fragmented rock. The inclusion of water has an effect as well.

Vester, Robert (VDOT), 2025-09-05T14:50:22.028

Subsurface Exploration






Subsurface Exploration – Rock Quality

- Upper 20 to 30 feet (Abutments and Pier 1, 4, 5, 6, and 7):
 - highly fractured
 - RQDs ranging 0 to ~40%, predominantly zero RQD in this upper zone indicating poor quality rock.
- Below 20 to 30 feet:
 - Rock quality improvement
 - RQDs generally >40%.
- Pier 2 and 3 borings
 - RQDs predominantly >50% below 5 feet depth of rock.




Subsurface Exploration – Sample Fence Diagrams





Subsurface Exploration – Sample Fence Diagrams





Subsurface Exploration - representative rock cores







Geology – GDR comments

From GDR (consultant): _{VRO}

- The IGM/rock is highly fragmented with interbedded strata that are more or less susceptible to wash out during coring.
- This can be attributed to: presence of phyllite (relatively soft and susceptible to washout); fracturing and differential weathering in metasandstone.
- We have differentiated IGM and rock using core recovery and RQD rather than auger/sampler refusal.



If this is directly from the GDR then these statements should have quotes around them. Vester, Robert (VDOT), 2025-09-05T14:46:19.885 VR0

Design - general considerations

- Due to relatively high loads, the presence of rock, the anticipated scour depths and the desired column extension pier design, drilled shafts were determined to be the most appropriate foundation type.
- Scour and the highly fractured rock were the major drivers in drilled shaft design.
- Only side resistance was used for axial resistance Pesign required 30 ft rock socket length for all except Pier 2 and 3 that required 22 ft rock socket length. Rock socket diameter is 5.5 ft for all shafts.
- Permanent steel casing specified for all drilled shafts in river per design requirement (Piers 2,3,4 added for Pier 1 during CN)



VR0

We may be asked whether we considered a combination of side and end bearing. My answer for that is that you can't maintain a clean bottom to count on mobilizing the end bearing due to the highly fragmented rock.

Vester, Robert (VDOT), 2025-09-05T15:13:49.763

Design - parameters for highly fractured rock and rock

Highly fractured rock parameters for all substructures except Pier 2 and 3:

- RQD = 0 (Joint Modification Factor, $\alpha_E = 0.3$) (AASHTO 10.8.3.5.4b)
- Rock Compressive Strength = 2,900 psi (lab tests)
- Rock Unit Weight = 140 pcf (lab tests, all substructures)
- Rock Mass Elastic Modulus = 1758 ksi (lab tests, all substructures)

Rock parameters for Pier 2 and Pier 3:

- RQD = 50 (Joint Modification Factor, $\alpha_E = 0.55$) (AASHTO 10.8.3.5.4b)
- Rock Compressive Strength = 7,400 psi (5,000 psi A5 concrete controls)



Design - skin friction in highly fractured rock

 Unit Skin Friction (q_s) is based on RQD and joint conditions (AASHTO LRFD 8th Ed. Section 10.8.3.5.4b)

$$\frac{q_S}{p_a} = 0.65\alpha_E \sqrt{\frac{q_u}{p_a}}$$


$$p_a = \text{atmospheric pressure taken as } 2.12 \text{ ksf}$$

$$\text{qu = uniaxial compressive strength of rock or concrete, whichever is less, ksf}$$

AASHTO Table 10.8.3.5.4b-1 used to determine value of α_E

Table 10.8.3.5.4b-1—Estimation of α_E (O'Neill and Reese, 1999)

	Joint Modification Factor, α_E	
		Open or
RDQ (%)	Closed Joints	Gouge-Filled Joints
100	1.00	0.85
70	0.85	0.55
50	0.60	0.55
30	0.50	0.50
20	0.45	0.45




• For RQD of zero, $\alpha_E = 0.3$ based on graphical extrapolation


Design - scour considerations

- Current VDOT scour policy is per HEC-18 and assumes rock with RQD<50% is scourable.
- Total design scour depths (100 yr flood):
 - Abut A = 29 ft
 - Piers 2,3,4 = 23 to 42 ft
 - All others = 8 to 12 ft




Drilled Shaft Plans (North half of bridge)







Drilled Shaft Details - Piers



1504

102

29.50*

53

30.0*



DRILLED SHAFT ELEVATION

Pler 7

Temporary

* The Strength Limit State controls the drilled shaft design.

318.5

317.5

299.5

Right

17,50*

Drilled Shaft Special Provision (including CSL testing)

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

VIRGINIA DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION FOR DRILLED SHAFTS

October 3, 2023

0092-019-860, B607, C501

I. DESCRIPTION

This work shall consist of all labor, materials, equipment, and services necessary to perform all operations to complete the drilled shaft installation in accordance with the Specifications, this Special Provision, and with the details and dimensions shown on the Plans, and as directed by the Engineer. Drilled shafts are reinforced concrete, deep foundation elements, cast-in-place against insitu material through augment holes. Unless otherwise shown on the Plans, drilled shafts are straight and vertical.

II. SITE INFORMATION

If Engineering Geology Sheets are included in the Contract Documents, the data on subsurface conditions are not intended as representations or warranties of continuity of such conditions. The data is made available for the convenience of the Contractor, and it is expressly understood that the Department will not be responsible for interpretations or conclusions grawn there from.

The Contractor or prospective bidders may obtain, prior to bidding, right-of-entry and complete whatever investigations, research, tests, or analyses required for bid purposes.

If a geotechnical report was prepared for this project, this report was prepared to establish design guidelines only and is not considered part of the Contract Documents or a warranty of subsurface conditions. The opinions and engineering analyses expressed in the report are those of the authors, and they represent their interpretation of subsurface conditions, and field and laboratory test data. Therefore, the information in the Geotechnical Report is not intended as a substitute for the Contractor's personal investigation, interpretation, and good/udgment.

III. QUALIFICATIONS OF DRILLED SHAFT CONTRACTOR

The Drillor Shaft Contractor performing the work described in this Special Provision shall-have experience consisting of successful installation of at least ten drilled shaft projects installed within the past 5 years, two of which shall be similar or greater size and in similar geologic condisons. The Drillor Shaft Contractor shall people decommentation of his superintendent's quantifications, record of experience, and prior project seprences demonstrating that he can begin guestion under the supervision of the Drillor Shaft Contractor's superintendent, who shall have at least 5 years of experience installing drilled shafts within the last 8 years and shall be fully sourfidepeable and experienced in construction of drilled shaft foundations of similar size and geologic conditions as those shown on the Plans.

The mentioned documentation shall reference, for each project, the names and phone numbers of owner's representatives who en venify the Drilled Shalf Contractors, participation on those projects, detail the size and number of the shalts, methods used during installation, methods used for wall stabilization, local poll conditions, actual construction time, and contract time.

The Engineer may accept or reject the Drilled Shaft Contractor and/or Superintendent-based on higusaffications and previous field performance.

QUALIFICATIONS OF DRILLED SHAFT CONTRACTOR{ TC "QUALIFICATIONS OF DRILLED SHAFT CONTRACTOR $_2\text{-}9\text{-}24$ (SPCN)" If C \| "1" \}

The Contractor is advised that Part III Qualifications of Drilled Shaft Contractor in the Special Provision for Drilled Shafts dated 10-3-23 are waived by the Department and will not apply to the acceptance or rejection of the Drilled Shaft Contractor, however the Contractor shall take the Drilled Shaft Contractors qualifications into consideration towards the performance of the work.

All other Drilled Shaft Contractor requirements in the Special Provision apart from those noted in **Part III**Qualifications of Drilled Shaft Contractor, shall be enforced as part of the Contract

The Contractor shall discuss the Qualifications of the Drilled Shaft Contractor at the General and/or Drilled Shaft Pre-Construction Conferences.

2-9-24 (SPCN)

2. Crosshole Sonic Logging (CSL) Test

A. General

Crosshole Sonic Logging (CSL) is a nondestructive testing (NDT) method that measures the time for an ultrasonic pulse to travel from a signal source inside an access tube an excess tube and evaluates the integrity of drilled shafts. In uniform, good quality concrete, the travel time between these equidistant tubes will be relatively constant from the bottom to the top of the drilled shafts and correspond to a reasonable concrete pulse velocity. In uniform, good quality concrete, the CSL test will also produce records with good signal amplitude and energy. Longer travel times and lower amplitude or energy signals indicate the presence of irregularities such as poor-quality concrete, voids, honeycombs, or soil intrusions. The signal will be completely lost by the receiver and system recorder for more severe defects such as voids and soil intrusions.

The Contractor shall install access tubes intended for CSL testing and perform the tests as indicated in the Plans and described herein. When the Contractor is required to perform CSL tests in the Contract, he must only employ experienced personnel and engage the services of approved independent testing firm with previous experience in CSL testing. The Contractor shall submit to the Engineer for his approval the list of personnel and testing firms he intends to use during the CSL testing program along with their competence and field experience to perform evaluate and report the results of CSL tests. The Contractor shall perform the CSL

tests in the number and locations specified or as requested by the Engineer, and he shall execute the test at least 48 hours after the completion of concrete placement of a given drilled shaft. The Engineer may specify a longer waiting period when retarders are used in the mix design, or other factors that may result in a slower rate of concrete setting. All CSL testing must be completed within 45 calendar days of concrete placement of a given drilled shaft.

Prior to beginning the CSL test, the Contractor shall assure that the test probes can pass arough and down the tubes to the bottom of every installed tube. If a tube is obstructed, the contractor shall core a hole large enough to accommodate the probe through its full length in he drilled shaft and near the obstructed tube to the depth indicated in the Plans for that CSL ube. If required, coring to accommodate CSL testing shall be at no additional cost to the Department. Core equipment, procedure, and location of the hole shall be approved by the ingineer prior to beginning coring. Logged results of the core drilling shall be submitted to he Engineer along with the cores. The CSL test may commence after the core hole is aspected and the probes can pass through.

The Contractor is responsible for submission of the CSL test report to the Engineer within 5 vork days of its performance for a specific drilled shaft. The Engineer will evaluate and nailyze the CSL test results within 3 working days of their receipt and provide the Contractor vith a response regarding the acceptability of the drilled shaft tested.

142



Criteria for Top of Rock Socket Determination

Defined in VDOT Special Provision by penetration rate:

3. Rock Socket

Rock Socket is defined as excavation that is accomplished using the same drilling equipment described in "Special Excavation," operating at full torque and crowd, where the penetration is equal to or less than 1/2-inch in 5 continuous minutes of operation. The drill rig shall be in good condition and shall be capable of applying a minimum crowd of 35,000 pounds while turning the auger for diameters equal to or less than 48 inches, and at least 50,000 pounds of crowd for augers greater than 48 inches in diameter. The Contractor shall provide the Engineer with access to the instrument gauges in order to confirm that full torque and crowd are being applied.

When Rock Socket is specified as a pay item and detailed on the Plans, the Contractor shall provide the minimum penetration into rock as shown on the Bridge Plans, unless field modified by the Engineer.



TIP testing Special Provisions

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

VIRGINIA DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION FOR THERMAL INTEGRITY PROFILING (TIP) OF DRILLED SHAFTS

July 30, 2023

0092-019-860, B607

I. DESCRIPTION

Thermal Integrity Profiling (TIP) uses the heat generated by curing cement (hydration energy) to assess the quality of drilled shafts. The expected temperature at any location is dependent on the shaft diameter, mix design, time of measurement and distance to the center of the shaft. TIP measurements may be used to estimate the actual shape of the shaft as well. These estimates may be compared with concreting logs to assess the overall quality of the shaft. Good communication between the Contractor, the Drilled Shaft Contractor and TIP Consultant is essential.

TIP measurements that are colder than normal indicate necks, inclusions, or poor quality concrete, while warmer than normal measurements are indicative of bulges. Variations of temperatures between wires reveal cage eccentricity.

II. QUALIFICATIONS FOR TIP CONSULTANT

The TIP consultant shall have a licensed professional engineer holding a valid license to practice engineering in the Commonwealth of Virginia who is experienced in supervising the testing and interpreting the results. The TIP Consultant shall be an independent testing agency with documented and approved experience in TIP testing on at least five projects of similar or greater scope within the last 2 years. The Consultant qualifications and a description of the equipment used shall be submitted to the Engineer for approval at least 21 calendar days prior to beginning drilled shaft installation. For each project cited, the names and phone numbers of owner's representatives who can verify the TIP Consultant's participation on those projects shall be provided. Within 14 days after receipt of the installation plan, the Engineer will notify the Contractor of any additional information required or changes necessary to meet the Contract requirements.

III. ASSISTANCE BY THE DRILLED SHAFT CONTRACTOR TO THE TIP TESTING CONSULTANT

The Drilled Shaft Contractor shall provide cooperative assistance, suitable access to the site and the drilled shafts to be tested, and labor as required to assist the TIP Consultant in performing the required tests. Prior to testing, provide the drilled shaft lengths and dates of construction of drilled shaft to the TIP Consultant and coordinate with TIP Consultant to install the necessary TIP instrumentation prior to concretion the shaft.

IV. EQUIPMENT REQUIREMENTS FOR TIP

The equipment shall have the following minimum requirements:

- A computer-based TIP data acquisition system to monitor temperature versus time after casting.
- (2) Ability to collect data at user defined time intervals (typically 15 to 60 minutes).









TIP photos courtesy of PDI



Bid Phase

 Language in contract required bidders to visually inspect the rock core boxes at the Lynchburg District office prior to bidding.

MANDATORY PRE-BID GEOLOGY BORING ROCK CORE SAMPLE REVIEW – Bidders are advised there will be a **mandatory** Pre-Bid Geology Boring Rock Core Sample Review held at the District Office. Admission to the mandatory Pre-Bid Geology Boring Rock Core Sample Review will be conditioned upon the following:

- Date and Time: Review to be scheduled and completed by Bidder no later than 5:00 PM on June 5th, 2024
- Location: Lynchburg District Office
- Point of Contact for scheduling review: James "Rusty" Hall, P.E. (District Geologist)
- Phone: 434-841-7376
- Email: James.Hall@VDOT.Virginia.gov
- A photo-ID will be required (example: a valid Driver's License or a valid passport).

Bids will only be accepted from those bidders who are represented at this mandatory Pre-Bid Geology Boring Rock Core Sample Review. Bidders should anticipate a week duration between notifying James "Rusty" Hall of scheduling a time and the actual meeting date. Attendance at this mandatory showing will be evidenced by the representative's signature on the Department's attendance roster.

Bidders are invited to bring a copy of the solicitation proposal with them. Any changes resulting from this mandatory Pre-Bid Geology Boring Rock Core Sample Review will be issued in a written addendum to the solicitation proposal.



Construction - Installation Plan

1.4. Tooling

- 1.4.1. 66" and 72" Nominal Diameter Drilling Tools
- 1.4.2. Dirt augers
- 1.4.3. Rock augers
- 1.4.4. Core barrels, roller barrels, air barrels
- 1.4.5. Slurry augers
- 1.4.6. Drilling Buckets
- 1.4.7. Cleanout buckets
- 1.4.8. Excavation grab tools

1.9. Construction


- 1.9.1. Temporary Casings Smooth wall, rolled and welded pipe. 74" Nominal ID, 0.500" wall, will be used as temporary casings. *The pipe meets ASTM A252 specifications*.
- 1.9.2. Permanent Casings Casings will conform to ASTM A242, 46 ksi. Casings will be shipped and installed at full length.
- 1.9.3. Permanent Casings 72" OD x 0.75" wall, ordered lengths 30' to 46'

Polymer Slurry Specifications, SP X.2.

Property at 70°F (Units)	At the Time of Slurry Introduction in the Drilled Shaft, During Drilling and Before Concrete Placement in the Drilled Shaft	Test Method
Density in Fresh Water ^a (lb/ft ³)	64 maximum	Mud Weight (Density) API 13B- 1, Section 1
Viscosity (sec per quart)	32 to 135	Marsh Funnel and Cup API 13B- 1, Section 2.2
pH	8 to 11.5	Glass Electrode, pH meter or pH paper Strips
Sand Content ^b (%)	1.0 maximum	Sand API13B-1, Section 5












Construction - Access causeway





Construction - Access Causeway





Construction - Trial Shaft

- Contractor requested to make trial shaft the first production shaft at an abutment. This was agreed to at the contractor's risk.
- Trial shaft was at Abut B, did not have permanent casing.
- Initial pour issues with concrete mix design and admixtures. First 5 trucks were not accepted due to being out of spec for slump flow and air content.
- Second attempt to pour was successful with only a minor issue at the very top of the trial shaft starting to set.
- Contractor performed PIT to evaluate top 1-2 feet of trial shaft.




Construction – Trial Shaft Installation








Construction - CSL and TIP testing - typical layout







Construction - CSL test results - trial shaft







Construction – TIP testing results - trial shaft









Construction - CSL test results - production shafts






Construction - TIP testing results - production shafts










RV0 Note that this drilled shaft shows evidence of bulging below the casing. Rock socket is designed to be narrower by 6 inches but we lose concrete into the fractured rock.

Vester, Robert (VDOT), 2025-09-10T19:52:44.362













Lessons learned

- Require contractors to view rock cores in person pre-bid
- Rock penetration rate in SP is key. Highly fractured hard rock behaves similar to unfractured rock
- Highly fractured rock characterization/investigation insitu testing - rock borehole shear test (RBST)??
- Consider MWD and/or sonic drilling
- Specify load test (bi-directional load cell or similar) in contract??



Construction - Collaboration

- Close coordination/collaboration was key between:
- Lynchburg District (S&B, Materials, CN, Environmental)
- CO S&B Geotechnical
- Contractor
- Drilled shaft Subcontractor
- Mother Earth



Questions???

"In theory there is no difference between theory and practice. In practice there is." *Yogi Berra*







Geology

From GER:


- We have differentiated IGM and rock using core recovery and RQD rather than auger/sampler refusal.
- We have characterized the materials below refusal but above interpreted TOR as non-friable IGM.
- Non-friable IGM descriptions should be used with caution as they only represent the more competent, recovered core and do not represent the strata washed out during coring.



Current VDOT Scour Policy

- Current VDOT scour policy is to assume rock with RQD<50% is scourable (very conservative).
- Scour design is per HEC-18.
- Consideration is being given to allowing the use of the Erodibility Index Method (Annandale method) for scour in fractured rock (at piers only) on future projects. EIM was

not used for this project.






Design - scour considerations


- Current VDOT scour policy is per HEC-18 and assumes rock with RQD<50% is scourable.
- Total design scour depths (100 yr flood): 29 ft in Abut A, 23 to 42 ft in Piers 2 to 4 and 8 to 12 ft in all other substructures. (Depths referenced from

bottom of pile cap for abutments and top of drilled shaft for piers)





Drilled Shaft Details - Abutments



				DATA TABLE								
6.4.4			Elevo	rtions	Otwensions		Required Nominal	Required Factored	060801		060102	
Substructure	Shoft	*Location	Diev. TS	Dev. TR	Çim, "HI"	Din. 142* minimum	Axial Resistance •*(Tons/shaft)	Axiat Resistance ★● (Tons/shaft)	×	Y	, a	к
	- 1	Left wingwat	326.9 296.0		30.4"	30.0*			102	29.50*	100	33.12*
	2	Right wingwall	254'8	296.0	30.4"	20.0]		105	29.50*	100	22'15.
Abutment A	3	Left, main ftg.	324.9	296.0	30.4"	30.0*	1504	827	102	29.50*	100	33.12*
	4	Center, main ftg.	326.9	296.0	30.4"	30.01			102	29/50*	100	33.12*
	5	Right, main ftg.	324.9	296.0	30.4"	30.0*	1		105	29.50*	100	33.12"
	20	Left, main ftg.	326.9	266.0	60.4"	30.0*			102	29.50*	190	63.10*
	21	Center, main ftg.	324.9	266.0	60.4"	30.01]		105	29.50*	190	62'10.
Abutment B	22	Right, main ftg.	326.9	266.0	60.4"	30.0*	1504	827	102	29.50*	190	63.10*
	25	Left wingwall	326.9 266.0		60.4"	30.01]		105	29.50*	190	62'10.
	24	Right wingwall	324.9	246.0	60.4"	30.0*	1		105	29.50*	190	63.10*

^{*} Location is relative to Constr. & Rite. 92. See sheets 20 and 28 for drilled shaft identification.



DRILLED SHAFT ELEVATION

^{**} The Strength Limit State controls the drifted shaft design.

TIP testing Special Provisions

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

VIRGINIA DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION FOR
THERMAL INTEGRITY PROFILING (TIP) OF DRILLED SHAFTS

July 30, 2023

0092-019-860, B607

I. DESCRIPTION

Thermal Integrity Profiling (TIP) uses the heat generated by curing cement (hydration energy) to assess the quality of drilled shafts. The expected temperature at any location is dependent on the shaft diameter, mix design, time of measurement and distance to the center of the shaft. TIP measurements may be used to estimate the actual shape of the shaft as well. These estimates may be compared with concreting logs to assess the overall quality of the shaft. Good communication between the Contractor, the Drilled Shaft Contractor and TIP Consultant is essential.

TIP measurements that are colder than normal indicate necks, inclusions, or poor quality concrete, while warmer than normal measurements are indicative of bulges. Variations of temperatures between wires reveal cage eccentricity.

II. QUALIFICATIONS FOR TIP CONSULTANT

The TIP consultant shall have a licensed professional engineer holding a valid license to practice engineering in the Commonwealth of Virginia who is experienced in supervising the testing and interpreting the results. The TIP Consultant shall be an independent testing agency with documented and approved experience in TIP testing on at least five projects of similar or greater scope within the last 2 years. The Consultant qualifications and a description of the equipment used shall be submitted to the Engineer for approval at least 21 calendar days prior to beginning drilled shaft installation. For each project older, the names and phone numbers of owner's representatives who can verify the TIP Consultant's participation on those projects shall be provided. Within 14 days after receipt of the installation plan, the Engineer will notify the Contractor of any additional information required or changes necessary to meet the Contract requirements.

III. ASSISTANCE BY THE DRILLED SHAFT CONTRACTOR TO THE TIP TESTING CONSULTANT

The Drilled Shaft Contractor shall provide cooperative assistance, suitable access to the site and the drilled shafts to be tested, and labor as required to assist the TIP Consultant in performing the required tests. Prior to testing, provide the drilled shaft lengths and dates of construction of drilled shaft to the TIP Consultant and coordinate with TIP Consultant to install the necessary TIP instrumentation prior to concreting the shaft.

IV. EQUIPMENT REQUIREMENTS FOR TIP

The equipment shall have the following minimum requirements:

- A computer-based TIP data acquisition system to monitor temperature versus time after casting.
- (2) Ability to collect data at user defined time intervals (typically 15 to 60 minutes).

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

V. SHAFT PREPARATION FOR THERMAL WIRES

All shafts shall be equipped with a minimum of one thermal wire for every 1 foot of drilled shaft diamete. The number of thermal wires shall be rounded up in the case of shafts not of whole foot diameters an a minimum of four wires shall be used for shafts with diameters of 3 feet. The wires shall be even spaced.

Thermal wires shall be aligned with the longitudinal reinforcement of the shaft and stretched to minimiz the wire slack. The wires shall be tied at intervals not exceeding 3 feet to the reinforcement at a locatio on the reinforcement that is 90 degrees to the line connecting the reinforcement to the center of the shaft.

VI. TIP PROCEDURE

Thermal wires shall be connected to a Thermal Access Port (TAP) prior to casting concrete to assess that the thermal wires were not damaged during placement of the reinforcing steel cage. Damaged thermal wires prior to casting concrete shall be replaced immediately. Data shall be collected by the TAP every 15 minutes for 24 hours, or as recommended by the TIP Consultant. After completion of the data collection period, the TAP shall be connected to the main TIP data acquisition unit and the data files shall be downloaded for inspection of temperatures versus deoth.

Potential local defects indicated by locally low temperatures relative to the average temperature at that depth, or average temperatures significantly lower than the average temperatures at other depths, shall be reported immediately to the Engineer.

VII. TIP RESULTS

Results of the TIP shall be stamped by a Professional Engineer licensed in the Commonwealth of Virginia and presented in a written report within 5 working days of completion of testing. The report shall present results of TIP tests including:

- 1. Graphical displays of all temperature measurements versus depth.
- Indication of unusual temperatures, particularly significantly cooler local deviations of the average at any depth from the overall average over the entire length.
- The overall average temperature shall be reported. This temperature is proportional to the average radius computed from the actual total concrete volume installed (assuming a consistent concrete mix throughout). The radius at any point can then be determined from the temperature at that point compared to the overall average temperature.
- Report variations in temperature between wire (at each depth) which in turn correspond to variations in cage alignment. Where concrete volume is known, the cage alignment or offset from center should be noted.
- Where shaft specific construction information is available (e.g. elevations of the top of shaft, bottom of casing, bottom of shaft, etc.), these values should be noted on all pertinent graphical displays.

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

VIII. MEASUREMENT AND PAYMENT

Thermal integrity profiling (TIP) will be measured in units of each per drilled shaft tested and will be paid for at the contract unit price per each. This price shall include full compensation for all costs incurred and related to the TIP testing including, but not limited to, procurement, preparation and installation, conducting the tests, and subsequent reporting of results.

Payment will be made under

Pay Item	Pay Unit
Thermal integrity profiling (TIP)	Each



TIP testing Special Provisions

ORDER NO.: L02 CONTRACT ID. NO.: C0000111280B07

VIRGINIA DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION FOR THERMAL INTEGRITY PROFILING (TIP) OF DRILLED SHAFTS

July 30, 2023

0092-019-860, B607

I. DESCRIPTION

Thermal Integrity Profiling (TIP) uses the heat generated by curing cement (hydration energy) to assess the quality of drilled shafts. The expected temperature at any location is dependent on the shaft diameter, mix design, time of measurement and distance to the center of the shaft. TIP measurements may be used to estimate the actual shape of the shaft as well. These estimates may be compared with concreting logs to assess the overall quality of the shaft. Good communication between the Contractor, the Drilled Shaft Contractor and TIP Consultant is essential.

TIP measurements that are colder than normal indicate necks, inclusions, or poor quality concrete, while warmer than normal measurements are indicative of bulges. Variations of temperatures between wires reveal cage eccentricity.

II. QUALIFICATIONS FOR TIP CONSULTANT

The TIP consultant shall have a licensed professional engineer holding a valid license to practice engineering in the Commonwealth of Virginia who is experienced in supervising the testing and interpreting the results. The TIP Consultant shall be an independent testing agency with documented and approved experience in TIP testing on at least five projects of similar or greater scope within the last 2 years. The Consultant qualifications and a description of the equipment used shall be submitted to the Engineer for approval at least 21 calendar days prior to beginning drilled shaft installation. For each project cited, the names and phone numbers of owner's representatives who can verify the TIP Consultant's participation on those projects shall be provided. Within 14 days after receipt of the installation plan, the Engineer will notify the Contractor of any additional information required or changes necessary to meet the Contract requirements.

III. ASSISTANCE BY THE DRILLED SHAFT CONTRACTOR TO THE TIP TESTING CONSULTANT

The Drilled Shaft Contractor shall provide cooperative assistance, suitable access to the site and the drilled shafts to be tested, and labor as required to assist the TIP Consultant in performing the required tests. Prior to testing, provide the drilled shaft lengths and dates of construction of drilled shaft to the TIP Consultant and coordinate with TIP Consultant to install the necessary TIP instrumentation prior to concretion the shaft.

IV. EQUIPMENT REQUIREMENTS FOR TIP


The equipment shall have the following minimum requirements:

- A computer-based TIP data acquisition system to monitor temperature versus time after casting.
- (2) Ability to collect data at user defined time intervals (typically 15 to 60 minutes).





TIP photos courtesy of PDI






Subsurface Exploration – Sample Boring Logs



								-	٠		PROJECT #: 0092-019-860, UPC 111280 LOCATION: CHARLOTTE / HALIFAX COS.		BR-07		
		V	L		1		_		ı		STATION: 522+44 OFFSET: 16 ft		10)F 2	
		Virgini	Deg	part	ment	of Ti	remeg	orta	don		LATITUDE: 36.838101° N LONGITUDE:	78.667	701	W	
_		-		_		_		_	_	_	SURFACE ELEVATION: 308.0 ft COORD. DATU	_			
-	-	SOIL	ELL	סכ	ATA	<u>`</u>	PA	СК		_	Date(s) Drilled: 05/05/2021 - 05/06/2021 Drilling Method(s): NW CA / NQ DBL	LA	LAB DA		
		3011					r	DI			SPT Method: Auto Hammer (140 lb)		ă	3	
١	Ê	TEST WS	7 (%)	SAMPLE LEGEND	SAMPLE INTERVAL	CORE RECOVERY (%)	έz	Г	Г	STRATA LEGEND	Other Test(s): Not Applicable Driller: Connelly & Associates, Inc.	TM.	PLASTICITY INDEX	MOISTURE CONTENT	
2000	TO	BLON	WER	97.3	Ž.	Š	ATION	4	50	ž	Logger: C. Lewis, Schnabel Engineering	JWIT GNOT	10T	000	
3	ELEVATION (TI)	STANDARD PENETRATION TES HAMMER BLOWS	RECOVERY	WPL	MPLE	RE S	DESIGNATION	STRATA	JOINTS	PAT	GROUND WATER 2 FIRST ENCOUNTERED AT 1.8 TI DEPTH (Else, 306.2)	73	LAS.	385	
1	w	28.8	SOIL	3	20	8	88	S	7	50	NO LONG TERM MEASUREMENTS TAKEN			TSIO	
_		u.	95	\setminus	_	0	L	L	L	L	FIELD DESCRIPTION OF STRATA	LL.	PI	3	
4				Ш							0.0 / 308.0 AIR, barge reference elevation 22 inches above water				
4	305	1		Ш						Г	1.8 / 306.2 WATER, Staunton River	7		l	
,				Ш							and the symmetric transfer of the symmetry				
,				Ш											
1				Ш											
ł	300			П											
ļ		MAH	68	M	9					100	9.0 / 299.0	7		7.	
1		50/3 50/5	100	W	10.9					Ħ.	Alluvium, Brown, fine to coarse, POORLY GRADED SAND, very loose, wet (SP)	<i>/</i> rl		8.1	
2			1133	П	11.3					N	9.8 / 298.2 Residuum, Blue-gray, fine to coarse, SILTY GRAVEL, few sand,	71			
4	295	50/4	67	Ħ	13 13.3					W	very dense, wet, gravel includes flat and elongated rock fragments (GM)	П		11.	
1		50/2	0	Н	15 15.2					녆	10.5 / 297.5	'		ı	
6		50/2		Ш	17					H	IGM, Blue-gray, fine to coarse, SILTY GRAVEL WITH SAND, trace gravel, very dense, wet. (GM)			ı	
8	290	Surz	0	П	17.2					H	3 22 27 27 27			l	
ł		1		Ц	19.5					H	Casing Advancer Refusal at 19.5 ft.	4		ı	
٥		1		Ц	21	40	0				19.5 / 288.5	1		l	
2				Ш	-					Ĭ	/GM, Recovered core characterized as slightly weathered, moderately hard to hard, gray, METASANDSTONE			ı	
ď	285	İ		Ш		62	0			M	(19.5 to 27 ft., median core size cannot be reliably evaluated due to			l	
4				Ш							limited recovery)			l	
6				Н	26										
8	280			Ш							27.0 / 281.0 Slightly weathered to unweathered, moderately hard to hard, gray,	7			
1						78	40				METASANDSTONE, moderately fractured, slightly foliated, fine				
٥				U	31						grained, two joint sets dipping at about 40 to 50 and 70 to 80 deg., joints and fractures are healed with quartz, joints are generally				
2				П	31						planar and smooth to slightly rough, few second joint sets appeared rough, slickensides were noted on several joint faces, most core				
-	275					92	47				breaks appear mechanical from drilling, although fracture and joint infilling appears mostly spotty/weak including some spotty clay/ash				
4				Ш		ľ	1				coeting.				
6				H	36						(27 to 36 ft., median core size of recovered material 1.5 in.) SAME, highly fractured to moderately fractured below 34.8 ft				
ď											SAME, moderately fractured to incogrately fractured below 34.6 ft SAME, moderately fractured				
8	270					82	60				(36 ft. to total depth, RQD > 50)				
0	ADW	: Rig Type:	Dic	1	h D.6	0.00	9600	L			SAME, spotty calcite filled joints from about 37.5 to 38.5 ft.	1405	1.0	\	
	mino	r rog type.	Lie			0 (0	er ge	1			μ.	BR			









Construction - Access Causeway





Construction - Trial Shaft Installation










































Construction



